Zero Waste Fife









Contents

- Who we are
- Kerbside Recycling
- Waste Treatment
- Organic Waste Treatment
- Consultancy Services





Who We Are

- Fife Council
 - 11th largest in the UK
 - 3rd largest in Scotland
 - 375,000 people
 - 16,000 employees
 - Annual revenue budget approaching £1bn

- Sustainability Unit
 - £20 million turnover
 - 55 employees
 - £7 million external income
 - Zero Waste
 - Climate Change Mitigation
 - Waste Treatment and Disposal
 - Energy Generation and Supply
 - Climate Change and Zero Waste Consultancy





Zero Waste

Kerbside Recycling





Previous 3 Bin Kerbside Service

2 weekly x 240 L



Garden Waste

2 weekly x 140 L



Paper & Card

2 weekly x 240 L



Landfill Waste





New 4 Bin Kerbside Service







4 Bin Service Outcomes

Material	Result
Food Waste (kg/hh/wk)	1.7
Garden Waste (kg/hh/wk)	4.6
Paper & Card (kg/hh/wk)	2.3
Cans & Plastics(kg/hh/wk)	0.8
Landfill (kg/hh/wk)	4.3
Total (kg/hh/wk)	12.0
Recycling Rate	64%
Satisfaction Rate	93%





Waste Treatment & Disposal





Waste Treatment & Disposal

- Landfill 250,000 tonnes/yr of waste at 2 landfills
 - Including 10,000 tonnes/yr of asbestos
- Produce up to 20,000 tonnes/yr of PAS 100 green waste compost at 2 sites
- 40,000 tonne/yr AD plant due to open in summer 2013











Waste Treatment & Disposal

- Operate 2 MRFs for mixed skip waste
- Waste water treatment plant
- Recycle 55% of municipal waste, including
 - >20,000 tonnes of paper & card
 - >30,000 tonnes of green waste
 - 6,000 tonnes of cans & plastics
 - 8,000 tonnes of glass
 - 13,000 tonnes of wood
 - 3,000 tonnes of scrap











Organic Waste Treatment Review 2008

- Had just completed roll out of 3 bin system
- Recycling rate increased to 39%
- Commissioned a study into MBT of residual waste followed by AD of organic fraction
 - Too many risks and too much uncertainty
 - Emerging ZW policy
 - Limited uses for digestates
 - Cost





2009

- Commissioned further work on treatment of food waste, garden waste and sewage sludge
 - 2 site option
 - Evaluation of technology options, costs and benefits
- Began testing food waste collection options
 - Quickly took a view that co-mingled with garden waste was more sustainable
 - Financially
 - Environmentally
 - Also provides an additional renewable power feedstock






2010

- Further evaluation of AD options for treatment of co-mingled food and garden waste.
 - Dry AD clearly most appropriate
 - Indicative costs and benefits very attractive
 - Significant potential financial benefits of in house operation
 - Range of dry AD technology providers available
 - Reference plants visited
 - Appeared to do what they said on the tin
 - Nothing scary re plant operation
 - "Driest" systems have significant similarities with existing waste handling activities









Outcome of 2010 Evaluation

- Enough info to make a decision re technology, and scale
- Reasonable forecasts re costs and benefits
- Space available within PPC consented waste activity
- Grid connection and heat network
- Confidence in our ability to manage and operate a dry AD plant
- Reasonable forecast of anticipated green and food waste production
- Reasonable expectation of Prudential Borrowing if business case stacked up





Procurement

- Restricted Procedure
- Design and Build by contractor
- Operated by Council
- Contract based on ICME Red Book
- Supported by external technical consultants and Project Managers (SLR)
- Internal Finance, Legal, QS, Mechanical Engineering support









Key Dates

- First evaluation of options
 - 2008
- Start on site
 - April 2012
- Cold Commissioning
 - Late May 2013
- Hot Commissioning
 - Late June 2013
- Beneficial Use
 - October/November 2013
- Handover to Council
 - February/March 2014









Inputs & Outputs

- Development Budget
 - £15 million
- Feedstock
 - 40,000 tonnes food and garden waste
 - 3,000 tonnes Category 3 ABP waste
- Outputs
 - 1.4 MW electricity
 - 1.4 MW heat
 - Export to existing heat network
 - 18,000 tonnes PAS 100 compost
 - 5,000 tonnes liquid effluent









Lessons Learned

- Don't underestimate the time it takes
- We did not think of everything
 - Adds to cost and time
- SEPA are supportive but permitting has taken a long time
- External PM support essential
- High quality resident engineer essential
- Provides a degree of confidence re tackling other large waste infrastructure projects










Renewable Power

- Heat and Power from Landfill Gas
- Heat and Power from AD Biogas
- Wind Turbines
- PV
- Heat Networks







Consultancy – Zero Waste

- Waste compositional analysis
- Process audit
- Advice on waste minimisation
- Advice on opportunities for recycling
- Advice on waste segregation and storage
- Project management of delivery of new services







Consultancy - Carbon & Climate Change

Audit

- Carbon Emissions Audits and Footprinting
- Project and Programme 'Carbon Emissions Impact Assessments'
- Carbon Accounting systems
- Whole Life Costing

Planning

- Policy development (including Environmental Management Systems)
- Energy and Climate Change Strategies
- Carbon Management Plans
- Preparation of project business cases

Delivery Support

- Training groups and individuals
- Promotions and marketing campaigns
- Project management and delivery





Where Next?

- Residual Waste Treatment
- Review Options for Kerbside Improvements
- Expansion of Trading Activities
- Renewable Power Developments
- Heat Networks
- Consider New Delivery Model





Contact

Chris Ewing, Senior Manager (Sustainability)
07931 524436
chris.ewing@fife.gov.uk