Procuring in Partnership Recycling of Street Sweepings and Gully Emptying

APSE
Environmental Services Seminar
2015





Benefits

- Nearly 300,000 tonnes of material will be diverted from landfill by end of contract
- £10 million+ savings for 5 Midland waste disposal authorities
- Recycling rates for participating authorities boosted by around 3% per annum





Tender in a Nutshell

- Contract commenced Jan 2012
- 7 year term + up to 3 years extension
- Straight-to-gate for authorities other than WCC & CCC (transferred via SITA Coventry)
- 70% MINIMUM RECYCLING RATE (90%+ was anticipated)
- Disposal of residue at contractor's expense (incentive to achieve high recycling rate)
- Accepts both wet and dry materials from mechanical sweepers, gully tankers and mini sweepers.





Procurement

- £35/tonne benchmark price
- Open Tender (one stage)
- OJEU Advert May 2011
- Deadline for Tenders June 2011
- Contract award August 2011
- 9 showed interest
- 4 tender returns





Protocols & Game Plan

- Back-to-back / Joint Working Agreement with WCC required prior to separate bolton contracts direct with SITA from each named authority
- Max Tonnage = 30,500





Economy of Scale

- Warwickshire CC (lead) & Coventry CC
 PLUS
 - Staffordshire CC
 - Worcestershire CC
 - Leicestershire CC







Sweepings Tonnages

| Gully Emptyings etc | 1,500 |
|---------------------|--------|
| Sub Total | 29,000 |
| LCC | 1,500 |
| Worcs CC | 8,000 |
| SCC | 9,500 |
| CCC | 2,000 |
| WCC | 8,000 |





Coleshill Plant Processing

35K with Road Sweepings per year.

 The plant runs at 20m/t hour 5 day week, on a 10 hour day shift, 9 hours being

operational.





Coleshill Plant







Wolverhampton Plant







Street Sweeping Recycling

| Total Inputs | % Recycling v dried inputs |
|--|----------------------------|
| Aggregates recycled from roadsweepings | 13.4% |
| Sand recycled from roadsweepings | 39.8% |
| General Non haz Waste (Residual) for Recycling | 2.0% |
| General Non haz Waste (Residual) to Landfill | 0.1% |
| Mixed Metal Waste for Recycling | 0.1% |
| Sludge Recovered via soil improver for Landfill Restoration (using an approved EA Deployment) | 23.4% |
| Organics Recovered via soil improver for Landfill Restoration (using an approved EA Deployment/Permit) | 20.8% |
| Sludge (Taken to treatment works), includes 840m3 water adjustment i.e. for water added to the process | 0.4% |
| Summary % Recycling | 55.32% 44.6% |
| | 0.1% |





Usage of material

- Sand 11,200tpa (washed in effluent water so used in Landfill engineering layer)
- Sand 2,800tpa (used in block making on site – to supply SITA projects)
- Aggregates 3,850tpa (used in block making on site – to supply SITA projects)
- Organics 8,300tpa (restoration projects)
 via composting at Packington





Block Making









Conclusion

- Nearly 300,000 tonnes of material will have been diverted from landfill
- Excess of £10 million+ savings for 5
 Midland waste disposal authorities
- Recycling rates for participating authorities boosted by around 3% per annum for Municipal





Questions







Contact

glennfleet@warwickshire.gov.uk



